

Index

File No. V-14

T 4N R. 38E

Merid. W11

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)


R.D. Walla Walla County Umatilla

N.F. Umatilla State OR

Tract or Survey No. _____

Cor. No. _____

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

Found 2" Iron pipe with BC stamped as diagram 4" above ground. with a steel fence post 3ft. West.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

A 10" Fir bears S 29°E 29.0 Ft W1/16/534BT visible.
 A 12" spruce bears N 76°W 34.8 Ft W1/16/527BT visible.

PHOTO IDENTIFICATION DATA

Photo No. _____
 Filed At. _____
 Object Ident. _____
 Ident. By _____
 Signature _____

PLANE COORDINATE POSITION DATA

State _____ Zone _____
 X _____
 Y _____
 Estab. By _____
 Agency _____

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From Jct Rd #6401 with #64
 Go East on #64 1.3 mile to prv drive to north.
 Corner is North 1720'± from Rd #64

Signature G. Dennis Edward

Title LS Division _____ Headquarters Hormiston Date 7/19/85
 7100-52 (3. 68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

Painted Blazes on BT's Red & a red Band around
Attached 54-9 signs to BT's & to Fence Post.

Work Done By G. O. Edwards Title LS Date 7/19/85 State Registration No. 951
or Agency
Certified Cor. Record Prepared? Yes No Filed At: Pondtoton, OR Date 8/1/76

REMARKS

Index File No. V-17 T. 4N R. 30E M. 0111 Tract or Surv. No. Cor. 13

Index
 File No. V 14
 T 4 N R. 38 E
 Merid. Willamette

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

R.D. Walla Walla County Umatilla Tract or Survey No. _____ Cor. No. V 14
 N.F. Umatilla State Oregon

CORNER DIAGRAM

DESCRIBE CORNER MONUMENT FOUND



T 4 N R. 38 E
1 S 27
 W _____
16 S 34
 R.P.E. 2808
 1976

NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE

PHOTO IDENTIFICATION DATA

Photo No. _____
 Filed At. _____
 Object Ident. _____
 Ident. By _____

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

1.5 miles along Skyline road from Tollgate to road along transmission line. Thence easterly along transmission line 0.4 miles. Corner is north 900 feet.

PLANE COORDINATE POSITION DATA

State _____ Zone _____
 X _____
 Y _____
 Estab. By _____

James D. Hanley
 Signature
 Agency
 James D. Hanley

Title _____ Division _____ Headquarters _____ Date 7/14/76
 7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 2 $\frac{1}{2}$ " brass cap on a 2" iron pipe 31" long 4" above the ground with a 6' steel fence post 3' west with sign 54-4 attached.

9

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A fir 10" diam. bears S 29° E., 29.0 ft. dist marked W1/16 S 34 BT
 A spruce 12" diam. bears N 76° W., 34.75 ft. dist marked W1/16 S 27 BT

Each BT has a sign 54-3 attached 6" below a band of red paint and has a brass washer marked RPE 2808 nailed flush with BT blaze.

10

Work Done By. James D. Hanley Title Engineer Date 7/14/76 State Registration No. ORPE 2808
 or Agency _____

Certified Cor. Record Prepared ? Yes XX Filed At: Pendleton, Oregon Date 8/ /76 11

REMARKS

I buried a 1" x 24" pipe and I bent over and buried a steel fence post which were 3.5 ft. east of 1/16 corner.

Also, I attached sign 54-2 on S and W sides of a 12" fir alongside of corner monument.

12