


T 4 N R 38 E

History of original corner establishment:

Corner originally established by Frank W. Campbell under contract # 468 dated April 12, 1883. Set a 3" x 3 1/2" post marked 1/4 S on North face and a marked stone. from which:  
A 12" fir bears N 43° W 30 lks  
A 8" fir bears S 8° W 48 lks



In a U.S. Dependent Resurvey by Otis O. Gould in August 1939 the post was found and a 1" x 36" iron pipe with a brass cap marked as diagram was set 27" in ground. from which:

V-15

A 24" fir bears N 66° W 54 lks (35.6 ft)  
A 20" spruce bears S 21° E 72 lks (47.5 ft)

Description of corner evidence found:

Found 1" iron pipe with brass cap firmly in ground marked as diagram and a 3/4" iron pipe 3 ft above ground driven in beside it. from which:  
A 24" fir stump bears N 66° W 35.6 ft no blaze or marks visible  
A 20" spruce stump bears S 21° E 47.5 ft. part of blaze and some marks vis.

Description of monument and accessories established to perpetuate the original location of this corner:

I drove a steel fence post 3 ft S.W. of corner and attached a 54-4 sign. New bearing trees:  
A 7" fir bears N 70° E 8.5 ft. scribed 1/4 S 27 BT  
A 6 1/2" spruce bears S 19° W 19.5 ft. scribed 1/4 S 34 BT

I nailed alum. tags stamped 951 to bottom of blazes and painted blazes red. Painted red band around BT's and nailed USFS 54-3 and 54-4 signs to them.

I hereby certify the above corner location was perpetuated as herein described in July, 1985.

Jud Coppock Jud Coppock, Witness

REGISTERED PROFESSIONAL LAND SURVEYOR

G. Dennis Edwards

OREGON JULY 16, 1971 G. DENNIS EDWARDS 951

Office of..... County of.....  
State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....  
..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY  
Umatilla County Surveyor  
Date 8-6-85  
Rec'd By RA  
No. 85-103-R  
95-C