


History of original corner establishment:

James D. Hanley originally established this corner in July 1976 under contract # 004971N Set a 2"x 30" iron pipe with a brass cap stamped as diagram 24" in ground and placed a mound of stone to top. from which a 13" fir bears S 23° W 16.5 ft. no other BT's



V-16

Description of corner evidence found:

Found 2" iron pipe in mound of stone with B.C. stamped as diagram. from which a 13" fir bears S 23° W 16.5 ft. 1/16 S 34 BT visible. a steel fence post is driven 3 ft east of corner

Description of monument and accessories I established to perpetuate the original location of this corner:

New bearing tree; A 15" fir bears N 13° E 18.4 ft. scribed E 1/16 S 27 BT Note; the trunk of the above tree is bowed. the bearing and distance is taken to the center of the tree at the center of the blaze.

I nailed an alum. tag # 951 to the bottom of the blaze and painter both blazes red. Painted red bands around BT's and attached 54-3 and 54-9 signs.

Attached a 54-9 sign to fence post.

I hereby certify the above corner location was perpetuated as herein described in July, 1985

REGISTERED PROFESSIONAL LAND SURVEYOR

G. Dennis Edwards

OREGON JULY 15, 1971 G. DENNIS EDWARDS 951

Jud Coppock

Office of..... County of..... State of..... I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19..... by..... (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY Umatilla County Surveyor Date 8-6-85 Rec'd By RA No. 85-104-R 95-C