


V-16

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established this survey.



V-16

Description of corner evidence found:

Description of monument and accessories established to perpetuate the original location of this corner

Set a 2 1/2" brass cap on a 2" iron pipe 31" long 6" above the ground in earth and rock mound with signs 54-4 and 54-2 attached.

from which

A fir 13" diam. bears S 23° W., 16.5 ft. dist. marked E1/16 S 34 BT with a sign 54-3 attached 6" below band of red paint and a brass washer marked RPE 2808 is nailed flush with BT blaze.

No available trees in sec. 27.



Office of.....Surveyor..... County of.....Umatilla.....
 State of.....Oregon....., I hereby certify that the within Instrument was filed in this office
 for record on the 26 day of Aug., 1976.....
 (COUNTY OFFICIAL) by (DEPUTY)