


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

V-17

History of original corner establishment:

Frank W. Campbell under G.L.O. Contract No. 468, dated Apr. 12, 1883, set a basalt stone 12"x 12"x 10", 8" in the ground. Stone marked with 1 notch on S. and 2 notches on E. edges. From the corner: A Pine, 10" dia., N16°E, 116 lks. A Fir, 20" dia., S60°W, 175 lks. A Fir, 10" dia., N29°W, 85 lks.



Otis O. Gould under G.L.O. Special Instructions, Group No. 234, dated July 11, 1939, found a basalt stone 12"x 12"x 10" firmly set in a mound of stone from which: A Pine, 24" dia., N18°E, 84 lks. He set an iron post, 3' long, 2" dia., with brass cap mkd. per diagram. He marked new BTs: A Fir, 24" dia., S11°E, 564 lks. A Fir, 16" dia., S54°W, 204 lks. A Fir, 12" dia., N47 1/4°W, 122 lks.

Description of corner evidence found:

I found a 2" iron pipe with a 2 1/2" brass cap (G.L.O.) marked per diagram, firmly set in a mound of stone. From the corner:

Lodgepole Pine, 29" dia., N18°E, 55.4 ft.; scribing visible. Sawn stump, 2' dia., N47 1/4°W, 80.5 ft.; scribing visible. White Fir snag, 36" dia., S54°W, 134.6 ft.; scribing visible. Douglas Fir, 36" dia., S11°E, 372.2 ft.; healed blaze.

Description of monument and accessories established to perpetuate the original location of this corner:

I marked new BTs:

Spruce, 10" dia., N41°W, 94.8 ft.; mkd.: T4N R38E S27 BT White Fir, 11" dia., S32°W, 185.4 ft.; mkd.: T4N R38E S34 BT Lodgepole Pine, 8" dia., S1 1/2°E, 261.3 ft.; mkd.: T4N R38E S35 BT

BTs have blaze and a 6" band painted red, BT tags and "Land Survey Monument" signs. New BTs have, additionally, alum. "PLS 1832" washers nailed to the bottom of the blaze. There is a 6' steel fence post with a "Land Survey Monument" sign within 5' of the corner.

Measured to center of BTs using E.D.M. and staff compass. Magnetic declination set at 19 1/2°E.

Nov. 21, 1991



Office of..... County of..... State of..... I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19..... by..... (COUNTY OFFICIAL)

RECEIVED BY Umatilla County Surveyor Date 1-92 Rec'd By KK No. 92-01-R