


History of original corner establishment:  
None



W-14

Description of corner evidence found:  
None

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2" x 30" iron pipe 29" in ground with brass cap stamped as diagram. from which:  
a 6" fir bears N 4° E 7.7 ft scribed NW 1/16 S 34 BT  
a 5" fir bears S 43° 30' E 9.6 feet scribed NW 1/16 S 34 BT  
a 7" fir bears S 74° W 19.6 ft scribed NW 1/16 S 34 BT

I nailed alum. tags stamped 951 to bottom blazes and painted blazes red. painted red band around BT's and nailed USFS 54-3 and 54-9 signs to them.

Drove a steel fence post 3 ft East and attached a 54-9 sign.

I hereby certify the above corner location was perpetuated as herein described in July 1985.

Jud Coppock Jud Coppock

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*G. Dennis Edwards*

OREGON  
JULY 18, 1921  
G. DENNIS EDWARDS  
951

Office of..... County of.....  
State of..... I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....  
..... by .....

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY  
Umatilla County Surveyor  
Date 8-6-85  
Rec'd By KA  
No. 85-106-R  
95-C