


T 4 N R 38 E

History of original corner establishment:

Corner originally established by Frank W. Campbell under contract # 468 dated April 12, 1883. Set a 3 1/2 foot x 3" post marked 1/4 S on West face and a marked stone from which: a 12" fir bears S 42° W 107 lks a 18" fir bears N 49° E 82 lks



In a U.S. Dependent resurvey by Otis O. Gould in August 1939 he proportioned this corner in and set a 1" x 36" iron pipe with a brass cap marked as diagram from which: a 20" fir bears N 68° E 31 lks (20.5 ft) a 18" fir bears N 71 1/2° W 31 lks (20.5 ft)

Description of corner evidence found:

Found 1" iron pipe with brass cap stamped as diagram from which: a 20" down fir bears N 68° E 20.5 feet (root hole) partially healed blaze a 18" fir snag bears N 71 1/2° W 20.5 ft blaze rotted

Description of monument and accessories established to perpetuate the original location of this corner:

I drove a steel fence post 3 ft west and attached 54-4 sign New bearing trees a 10" fir bears N 80° E 22.2 ft scribed 1/4 S 34 BT a 23" spruce bears S 66 1/2° W 42.4 feet scribed 1/4 S 33 BT I nailed alum. tags stamped 951 to bottom of blazes and painted blazes red. Painted red band around BT's and nailed USFS 54-3 and 54-4 signs to them.

I hereby certify the above corner location was perpetuated as herein described in July, 1985

Jud Coppock Jud Coppock

REGISTERED PROFESSIONAL LAND SURVEYOR

G. Dennis Edwards

OREGON JULY 18, 1971 G. DENNIS EDWARDS 951

Office of..... County of..... State of..... I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19..... by..... (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY Umatilla County Surveyor Date 7-6-85 Rec'd By KA No. 85-98-R (85-95-C)