

Index

File No. X-15

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or

Survey No. _____

Cor.

No. C14

T 4N R. 38E

R.D. Walla Walla

County Umatilla

Merid. Will

N.F. Umatilla

State OR

CORNER DIAGRAM

↑
N
T4N R38E
C14 S34
1985
LS 951

DESCRIBE CORNER MONUMENT FOUND

NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE

PHOTO IDENTIFICATION DATA

Photo No. _____
 Filed At. _____
 Object Ident. _____
 Ident. By _____
 Signature _____

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From Jct Rd #6401 with #67
 Go East on Rd #67 1.6 mile to
 F.S. sign Type "A"
 Corner lies 215 ft. East of Type "A" sign.

PLANE COORDINATE POSITION DATA

State _____ Zone _____
 X _____
 Y _____
 Estab. By _____
 Agency _____

Signature J. D. Edward

Title LS

Division _____

Headquarters Hermiston

Date

7/19/85

7100-52 (3. 68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 2" x 30" Iron Pipe with Brass cap stamped as diagram 25" in ground in mound of stone. From which:

~~Set a steel fence post 5' East and attached 54-9 sign~~

Dravo a steel fence post 5' East and attached 54-9 sign

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

a 8" fir Bears S 23 1/2 E 22.3 ft scribed C 1/4 534 BT

a 10" spruce bears S 2 1/2 W 19.0 ft. scribed C 1/4 534 BT

nailed alum. tags stamped 951 to Btm Blazes & painted blazes red.

Painted red band around BT's and nailed 54-3 & 54-9 signs to them.

10

Work Done By G. D. Edwards Title LS Date 7/19/85 State Registration No. OR 951 or Agency

Certified Cor. Record Prepared? Yes No Filed At: Pendleton, OR Date 7/19/85

11

REMARKS

12

13