


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

- 17  
X-17  
T 4 N R 38 E

History of original corner establishment:

Corner originally established by Frank W. Campbell under contract # 468 dated April 12, 1883. Set a basalt stone 12"x10"x6", 8" in ground marked 1/4 on West face . from which:

A 10" fir bears S 80° E 12 lks  
A 12" fir bears N 85° W 82 lks



In a U.S. Dependent resurvey by Otis O. Gould in August 1939 the stone was found and a 1"x36" iron pipe with a brass cap marked as diagram was set 27" in ground with a mound of stone. Old BT A 32" fir bears S 65° E 12 lks (7.9 ft.) Old BT A 30" fir bears S 87 1/2° W 85 lks (56.1 ft.)

Description of corner evidence found:

Found 1" iron pipe with brass cap marked as diagram in a mound of stone. from which:  
A 36" fir bears S 65° E 7.9 ft. some marks vis. on chopped out blaze.  
A 33" fir bears S 87 1/2° W 56.1 ft Blaze Healed not opened.

Description of monument and accessories | established to perpetuate the original location of this corner:

I drove a steel fence post 3 ft. N.E. of corner and attached a 54.4 sign.

New bearing tree:

A 7" fir bears N 56° W 37.1 feet scribed 1/4 S 34 BT

I nailed an alum. tag to bottom blaze of new tree and painted all blazes red. Painted a red band around all BT's and attached 54-3 and 54-4 signs to them.

I hereby certify the above corner location was perpetuated as herein described in July, 1985

*Jud Coppock*  
Jud Coppock, Witness

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*G. Dennis Edwards*

OREGON  
JULY 18, 1971  
G. DENNIS EDWARDS  
951

Office of..... County of.....  
State of..... I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....  
..... by .....

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY  
Umatilla County Surveyor  
Date 8-6-85  
Rec'd By KA  
No. 85-101-R  
95-R