

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 4N, R 38E., W.M.


Corner Code No. X-3

Note: Monument marked as shown below

History of original corner establishment:

None. This corner was established as part of this survey.

Note that a 2" brass cap on a 1" iron pipe, origin unknown, was found near the true corner point but was rejected because it is out of position.



Corner No.  
Compass Declination: 19.0°

Description of corner evidence found:

Found, a 2" unrecorded brass cap on a 1" iron pipe, protruding 12" from a stone mound. Origin of the monument is unknown. This monument was rejected because it is considerably out of position--Bearing S 20°34' E 10.7' from the corner position as determined by this survey. The brass cap on the found monument is marked:  
 C 1/4  
 S31  
 1972

Description of monument and accessories established to perpetuate the original location of this corner:

At the position determined by survey, set a 2 1/2" aluminum cap on a 2 1/2" by 30" aluminum pipe, 15" in the ground and surrounded with a mound of earth and stone.

From the new monument, marked new bearing trees as follows:

A 9" alpine fir bears N 10°1/2 W 48.5' scribed C 1/4 S31 BT.  
 A 11" alpine fir bears S 43°1/2 W 66.5' scribed C 1/4 S31 BT.

Bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 and 54-9 and painted face of blaze and a 6" red band around each bearing tree.  
 Set steel fence posts South and West of corner and attached sign 54-2 to both posts and sign 54-9 to one post.



Office of Survey County of Umatilla  
 State of OR I hereby certify that the within instrument was filed in this office  
 for record on the 10<sup>th</sup> day of August, 1988  
David H. Rumbria by William R. Wells  
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Umatilla County Surveyor

Date 8-88

Rec'd By [Signature]

No. 88-43-R