

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


History of original corner establishment:

Corner established by George S. Pershin under G.L.O. contract number 304 dated Sept., 19, 1878.

Surveyor General's records state:

Set a pine post on SW slope for 1/4 sec cor from which:

- A fir 8" diam. bears N 70° E., 8 lks dist marked 1/4 S BT
- A fir 8" diam. bears S 05° W., 36 lks dist marked 1/4 S BT



2-3

Description of corner evidence found:

NONE

Description of monument and accessories established to perpetuate the original location of this corner

Set a 2 1/2" brass cap on a 2" iron pipe 31" long in earth and rock mound 6" above ground with a steel fence post 5' east with sign 54-4 and 54-2 attached. Also a steel fence post 3' south with a sign 54-2 attached.

new bearing trees:

A fir 12" diam. bears N 73° W., 33.0 ft. dist. marked 1/4 S 31 BT with sign 54-3 attached 6" below a band of red paint and a brass washer marked RPE 2808 is nailed flush with BT blaze.



Office of Surveyor County of Umatilla

State of Oregon, I hereby certify that the within instrument was filed in this office for record on the 26. day of August, 1976

..... by (DEPUTY)

(COUNTY OFFICIAL)