

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Index: Z-9

Corner Sec. 32 and 33, T.4N., R.38E., W.M.
 Original corner was set by Pershin in June 1879.
 His notes record:
 Set Fir post for cor. to sec. 32, 33, 4 and 5:
 A Tamarack 18 ins. di. brs. S.36°E. 32 lks. dist
 A Fir 8 ins. di. brs. S.48°W. 107 lks. dist
 A Tamarack 22" di. brs. N.30°W. 58 lks. dist

1	DIAGRAM	1
1		1
1	T4N R38E	1
1	S32 1 S33	1
1	-----	1
1	T3N R38E	1
1	S5	1
1	1939	1
1		1
1		1

In 1939, the GLO remonumented this corner.
 Their record reads:
 Set an iron post, 3 ft. long, 2 ins. diam., 27 ins.
 in the ground, with brass cap marked (diagram)
 from which

A pine, 20 ins. diam., brs. N.50 1/2°E., 15 lks. dist., marked T4NR38ES33BT.
 A Tamarack, 12 ins. diam., brs. N.61°W., 30 lks. dist., marked T4NR38ES32BT.

In 1982, PLS 933 added a bearing tree to this corner as described.
 A 18" Tamarack N16°E 29.3 ft. mkd T4N, R38E, S33 BT.

Description of corner evidence found:


Found the iron pipe as described with brass cap stamped as shown in the diagram. From this monument:

A 14" dbh Tamarack, N60°49'W, 19.1.' with healed blaze.
 A 18" dbh Tamarack, N16°59'E, 29.8', with open scribe blaze.


Description of monument and accessories I established to perpetuate the original location of this corner:

The bearings were based on the surveyed bearing between the 1/4 section corner and the southwest corner of section 32 as recorded by RPE 2808 in a filed Umatilla County survey. I set the following new witness trees:
 A 12" dbh Engleman Spruce bears S14°53'E, 13.4' scribed T4N R38E S35 BT;
 A 18" dbh Tamarack bears S11°47'W, 6.0' scribed T4N R38E S35 BT.
 An aluminum washer stamped RLS 852 is nailed between the letters B and T on each new tree. All four living trees have LSM and BT signs attached. Painted 6" red bands around all four living trees and painted the scribe blazes red.

This work was done July 11, 1992.



David L. Haddock



Office of _____ County of _____
 State of _____, I hereby certify that the within instrument was filed
 in this office for record on the _____ day of _____, 19____.

(COUNTY OFFICIAL)

(DEPUTY)

RECEIVED BY
 Umatilla County Surveyor
 Date 8-92
 Rec'd By KK
 No. 92-96-R