

USDA-FOREST SERVICE

Index
File No. L-23

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or
Survey No. _____ No. _____

T 4S R. 29E R.D. Ukiah County Umatilla
Merid. Willamette N.F. Umatilla State Oregon

64

CORNER DIAGRAM



T4S R29E

C 1/4 S 13

1981

PLS 848

DESCRIBE CORNER MONUMENT FOUND

Corner not previously established.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

N/A

PHOTO IDENTIFICATION DATA

Photo No. _____

Filed At _____

Object Ident. _____

Ident. By _____

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner is on a NE slope in timber.
A primitive road, running approx. N-S
is approx. 400 ft. West from corner.

Signature

Title
PLS 848

Division

Headquarters
Mt. Vernon

Date
9/10/81

7100-52-(3/68)

CORNER RECORD (PERPETUATION)

GPO 902-678

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set 3"x30" galv. iron pipe with 3" brass cap, stamped as shown on the diagram, set 24 inches in the ground.

From which

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A fir 14 inches dia. bears S72°W, 7.4 ft. scribed C 1/4 S 13 BT.
A tamarack 10 inches dia. bears S80°E, 40.9 ft. scribed C 1/4 S 13 BT.
Set steel posts with warning and boundary signs 5 ft. East and 5 ft. West from corner.
Nailed bearing tree signs and brass washers stamped PLS 848 to each tree.
Painted red band around each tree.

Work Done By D.M. Ferguson Title Surveyor Date 9/10/81 State Registration No. OR PLS 848
or Agency

Certified Copy Requested? Yes No Filed At: Umatilla Co. Surveyor Off Date

**PROFESSIONAL
LAND SURVEYOR**

REMARKS

Witnesses to above corner:

Mike Woodward
Jeff Smith

**OREGON
JULY 12, 1968
DOUGLAS M. FERGUSON
848**