

**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

E - 17  
DIAGRAM

**History of original corner establishment:**

The original corner was established by George S. Pershin on June 14, 1882, under GLO contract No. 430, as follows:

Set a stone, 20" x 12" x 6", and a post, in a mound of stone on level ground for corner to sections 2, 3, 10 and 11.

The stone is marked with 5 notches on the south and 2 notches on the east edges. The post is 4 feet long, 4 inches square and marked "T4S S2" on the northeast, "R30E S11" on the southeast, "S10" on the southwest and "S3" on the northwest.

T4S R30E  
S3|S2  
S10|S11  
PLS 1636  
2004

**Original corner evidence recovered:**

Found the original corner stone solidly set in the ground on the south edge of a mound of stones. The original corner stone is 19" x 13" x 6" and is plainly marked with at least three notches on the south edge. The marked stake of record is gone.

**Monument and accessories established to perpetuate the original position of this corner:**

In place of the corner stone, I set a 1" x 30" flared, galvanized iron pipe 26" into the ground. I bury the corner stone along the south side of the pipe and build a mound of stones around the pipe. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above, from which:

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S2", attached at ground level, bears N66° 30' E, 158.8 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 11", attached at ground level, bears S44° 30' E, 161.0 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 10", attached at ground level, bears S25° 30' W, 142.1 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S3", attached at ground level, bears N57° W, 99.4 feet.

I hereby certify the above corner point was perpetuated as hereon described on April 7, 2004. Magnetic declination set in compass: 18° E.  
NAD '83 UTM Zone 11 position: 5011953N, 337897E (plus or minus two meters).



Renews June 30, 2005

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY

Umatilla County Surveyor

Date 5-04

Rec'd By KK

No. 04-94-B