


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established in 1882 by George S. Pershin under General Land Office Contract No. 430. Surveyor General's notes states:
Set basalt stone 12 x 10 x 8 ins., 8 ins. in ground on level bench for 1/4 Sec. Cor. marked 1/4 on N side.
A pine 36 ins. dia. brs. N10°E 58 lks. dist. marked 1/4 S BT.
A pine 34 ins. dia. brs. S68°E 22 lks dist. marked 1/4 S BT.



E-23

Description of corner evidence found:

Searched for corner near midpoint between Sec. Cor. No evidence found. N-S fence runs through position of corner stone has probably been moved into a fence jack.

No bearing tree evidence found; an old fire has destroyed any trees, therefore, the position of the corner is determined by proportion.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 3"x30" galv. iron pipe with 3" brass cap stamped as shown in the diagram, set 16 inches in the ground and raised a mound of stone and earth around the pipe.

From which:

A pine 15 in. dia. bears S13°E, 91.5 ft. scribed 1/4 S 12 BT.

A pine 11 in. dia. bears N25°E, 2.8 ft. scribed 1/4 S 1 BT.

Set steel post with warning sign, N15°W, 5 ft. from corner.

N-S fence, 2 ft. East from corner.

Nailed bearing tree signs and brass washers stamped PLS 848 to each tree. Painted red band around each tree.

I hereby certify that the above corner monument was reestablished as herein described on 8/14/81.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Douglas M. Ferguson
OREGON
JULY 12, 1968
DOUGLAS M. FERGUSON
848

Witnesses: D. Mitchell Ferguson

Mike Woodward

Office of Co. Surveyor County of Umatilla
Oregon
I hereby certify that the within instrument was filed in this office
for record on the 12 day of January, 1982
David R. Krumbein by Betty Shatto
(COUNTY OFFICIAL) (DEPUTY)