


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner not previously established.



H-24

Description of corner evidence found:

N/A

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 3"x30" galv. iron pipe with 3" brass cap stamped as shown on the diagram. Set pipe 18 inches in ground and raised a mound of stone around the pipe.

From which:

A pine 16 inches dia. bears N43°W, 121.3 ft. scribed SE 1/16 S 12 BT.

A pine 14 inches dia. bears N86°E, 30.5 ft. scribed SE 1/16 S 12 BT.

Set steel posts with warning and boundary signs 5 ft. West and 5 ft. South from corner.

Nailed bearing tree signs and brass washers stamped PLS 848 to each tree.

I hereby certify that the above corner monument was established as herein described on 8/5/81.

Witnesses:

D. Mitchell Ferguson

Mike Woodward

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 12, 1968
DOUGLAS M. FERGUSON
848

Office of... Co. Surveyor... County of... Umatilla...

State of... Oregon... I hereby certify that the within instrument was filed in this office

for record on the... 7... day of... January... 1982

David Kaum... by Betty Shultz
(COUNTY OFFICIAL) (DEPUTY)

82-01-C

T-2