


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established in 1882 by George S. Pershin under general Land Office Contract No. 430
Surveyor general's notes state:
Set basalt stone 14x12x10 ins. and post 4 ft. long 4 in. square in mound of stone in open glade for corner to Sec. 7, 8, 17 & 18, Stone marked with 4 notches on S and 5 notches on E edges. Post marked with same and T4S S8 on NE, - R30E S 17 on SE - S 18 on SW and S7 on NW.



Handwritten mark

Description of corner evidence found:

Found 14x11x10 in. stone with 4 notches on South face and 5 notches on East face, set in a mound of stone, in E-W fence line.

No bearing trees originally established.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 3"x30" galv. iron pipe with 3" brass cap stamped as shown on the diagram, set 16 inches in the ground and raised a mound of stone and earth around the pipe.

No bearing trees available.

Set steel posts with warning signs 6 ft. East and 6 ft. West from corner.

I hereby certify that the above corner monument was reestablished as herein described, on 9/10/81.

Witnesses:

D. Mitchell Ferguson

Mike Woodward



Office of Co. Surveyor..... County of Umatilla
State of Oregon..... I hereby certify that the within instrument was filed in this office
for record on the 7th day of January, 1982
David B. Allen by Betty Stott
(COUNTY OFFICIAL) (DEPUTY)