


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established in 1882 by George S. Pershin under general Land Office Contract No. 430. Surveyor general's records state:
Set basalt stone 18x10x10 ins. in mound of stone in open glade on North slope for 1/4 Sec. Cor. Marked 1/4 on West face. No trees near.



L-9

Description of corner evidence found:

No evidence found. Fence running N-S & W. Construction and maintenance of fence over the years has destroyed the corner.

No trees originally taken.
Set corner position by proportion.

Description of monument and accessories established to perpetuate the original location of this corner:

Set 3"x30" galv. iron pipe with 3" brass cap stamped as shown on the diagram, set 14 inches in the ground and raised a mound of stone and earth around the pipe.

From which
A pine 11 in. dia. bears S20°W, 114.7 ft. scribed 1/4 S 17 BT.
A pine 9 in. dia. bears S63°E, 79.7 ft. scribed 1/4 S 16 BT.
Set steel posts with warning and boundary signs 5 ft. South and 5 ft. West from corner.
Nailed bearing tree signs and brass washers stamped PLS 848 to each tree.
Painted red band around each tree.

I hereby certify that the above corner monument was reestablished as herein described, on 9/16/81.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 12, 1968
DOUGLAS M. FERGUSON
848

Witnesses: _____
Dave Herburger

Larry Wyllie

Office of... Co. Surveyor... County of... Umatilla...
Oregon
State of... hereby certify that the within instrument was filed in this office
for record on the... 7th... day of... January... 1981
... Douglas M. Ferguson... by Billy J. Thall...
(COUNTY OFFICIAL) (DEPUTY)

82-2-B