

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:


Corner established in 1882 by George S. Pershin, under General Land Office Contract No. 430.

Surveyor General's records state:

Set basalt stone 12x10x5 in., 8 ins. in the ground on level for 1/4 Sec. Cor. marked 1/4 on N fc.

A pine 13 in. di. brs. N42°E, 26 lks. dist. marked 1/4 S BT.

A Pine 24 in. di. brs. S50°E, 58lks. dist. marked 1/4 S BT.



N-15

Description of corner evidence found:

Found 12"x10"x5" stone, when set upright marked 1/4 on North face, set in a circle of stone.

From which:

A pine 30" dia. with grown over blaze bears S24°E, 36.0 ft. (GLO notes call S50°E, 38 ft.). Pine is live in good condition.

A stump hole bears approx. N60°E, 13.0 ft.

(GLO notes call 13" pine, N42°E, 17.0 ft.)

Accepted center of stone as 1/4 cor. position.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 3"x30" galv. iron pipe with 3" brass cap, stamped as shown on the diagram. Set pipe 20 inches in the ground, set original stone alongside pipe and placed a small mound of stone around the pipe.

From which:

A pine 11 inches dia. bears N50°W, 13.4 ft. scribed 1/4 S 15 BT.

A pine 12 inches dia. bears S25°W, 33.4 ft. scribed 1/4 S 22 BT.

Set steel posts with warning and boundary signs 5 ft. East and 5 ft. West from corner.

Nailed bearing tree signs and brass washers stamped PLS 848 to each tree.

Painted a red band around each tree.

I hereby certify that the above corner monument was reestablished as herein described, on 9/81.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

[Signature]

**OREGON
JULY 12, 1968
DOUGLAS M. FERGUSON
848**

Witnesses: _____
Dan Martin

Dave Herburger

Office of..... Co. Surveyor..... County of..... Umatilla
State of Oregon..... I hereby certify that the within instrument was filed in this office
for record on the 7th day of January, 1982
David Krumholz by Betty Shedd
(COUNTY OFFICIAL) (DEPUTY)

82-02-B

T-2