


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner not previously established.



N-18

Description of corner evidence found:

N/A

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 3"x30" galv. iron pipe with 3" brass cap stamped as shown on the diagram, set 26in. in the ground.

From which:

A fir 6 in. dia. bears N4° W, 6.2 ft. scribed X BT.

A fir 10 in. dia. bears S17°W, 17.0 ft. scribed W 1/16 S 23 BT.

Set steel post with warning and boundary signs 5 ft. east and

5 ft. North from corner. Nailed bearing tree signs and brass

washers stamped PLS 848 to each tree.

Painted a red band around each tree.

I hereby certify that the above corner monument was established on 8/12/81 as herein described.

Witnesses: D. Mitchell Ferguson

Jeff Smith

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Douglas M. Ferguson
OREGON
JULY 12, 1968
DOUGLAS M. FERGUSON
848

Office of... County Surveyor..... County of... Umatilla
State of... Oregon..... I hereby certify that the within instrument was filed in this office
for record on the 22 day of January, 1982
..... Daniel H. Hummer..... by Betty Shultz.....
(COUNTY OFFICIAL) (DEPUTY)