

Index
File No. N-18

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or
Survey No. _____ Cor.
No. _____

T 45 R. 30E R.D. Ukiah County Umatilla
Merid. Willamette N.F. Umatilla State Oregon

CORNER DIAGRAM

T45 R30E
514
W1/16
523
1981
PLS 848



DESCRIBE CORNER MONUMENT FOUND

Corner not previously established.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

N/A

PHOTO IDENTIFICATION DATA

Photo No. _____
Filed At. _____
Object Ident. _____
Ident. By _____
Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____
X _____
Y _____
Estab. By _____
Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

A new road leading from the ridge road crosses a draw bottom approx. 1000 ft. West from corner. Corner is on the South side of the draw, approx. 150 ft. hor. from bottom.

[Handwritten Signature]

Title PLS 848 Division _____ Headquarters Mt. Vernon, OR Date 8/12/81 7100-52-(3.68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set 3"x30" galv. iron pipe with 3" brass cap stamped as shown on the diagram, set 26 in. in the ground.

From which:

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A fir 6 in. dia. bears N4°W, 6.2 ft. scribed X BT.
A fir 10 in. dia. bears S17°W, 17.0 ft. scribed W 1/16 S 23 BT.
Set steel post with warning and boundary signs 5 ft. East and 5 ft. North from corner.


Nailed bearing tree signs and brass washers stamped PLS 848 to each tree.
Painted a red band around each tree.

Work Done By D.M. Ferguson Title Surveyor Date 8/12/81 State Registration No. OR PLS 848
or Agency

Certified Correctly Prepared? Yes No Filed At Umatilla Co. Surveyor's Office Date 10/81

**PROFESSIONAL
LAND SURVEYOR**

REMARKS



**OREGON
JULY 12, 1968
DOUGLAS M. FERGUSON
848**

Witnesses to above corner:
D. Mitchell Ferguson
Jeff Smith