

USDA-FOREST SERVICE

Index

File No. ~~45~~ N-20

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or

Survey No. _____

Cor.

No. _____

T 45 R 30E

R.D. Ukiah

County Umatilla


Merid. Willamette

N.F. Umatilla

State Oregon

CORNER DIAGRAM

T45 R30E



DESCRIBE CORNER MONUMENT FOUND

Corner not previously established.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

N/A

PHOTO IDENTIFICATION DATA

Photo No. _____

Filed At. _____

Object Ident. _____

Ident. By _____

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner is on North side of open ridge approx. 400 ft. North of primitive E-W road.

Signature

Title

Division

Headquarters

Date

7100-52-(3:68)

PLS 848

Mt. Vernon, OR

8/12/81

5

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set 3"x30" galv. iron pipe with 3" brass cap stamped as shown on the diagram, set 16 in. in the ground and raised a mound of stone around the pipe.

From which:

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A pine 11 in. dia. bears N44° W, 100.5 ft. scribed E 1/16 S 14 BT.
A pine 13 in. dia. bears S45° W, 63.9 ft. scribed E 1/16 S 23 BT.
Set steel posts with warning and boundary signs 5 ft. North and 5 ft. South from corner.
Nailed bearing tree signs and brass washers stamped PLS 848 to each tree.
Painted red band around each tree.

Work Done By D.M. Ferguson Title Surveyor Date 8/12/81 State Registration No. OR PLS 848
or Agency

Certified Registered Prepared? Yes No Filed At: Umatilla Co. Surveyor off. Date 10/81

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Douglas M. Ferguson
OREGON
JULY 12, 1968
DOUGLAS M. FERGUSON
848

REMARKS

Witnesses to above corner:
D. Mitchell Ferguson
Mike Woodward