


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner not previously established.



0-20

Description of corner evidence found:

N/A

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 3"x30" galv. iron pipe with 3" brass cap stamped as shown on the diagram, set 20 in. in the ground.

From which:

A pine 10" dia. bears N48°E, 6.8 ft. scribed NE 1/16 S 23 BT.

A pine 9" dia. bears S57°W, 12.4 ft. scribed NE 1/16 S 23 BT.

Set steel post with warning and boundary signs 5 ft. North and 5 ft. West from corner.

Nailed bearing tree signs and brass washers stamped PLS 848 to each tree. Painted red band around each tree.

I hereby certify that the above corner monument was established as herein described on 8/12/81.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Douglas M. Ferguson
OREGON
JULY 12, 1968
DOUGLAS M. FERGUSON
848

Witnesses:

D. Mitchell Ferguson

Mike Woodward

Office of... Co. Surveyor County of... Umatilla
State of... Oregon... I hereby certify that the within instrument was filed in this office
for record on the... 12... day of... January... 1981
Douglas M. Ferguson by Betty Shatto
(COUNTY OFFICIAL) (DEPUTY)

82-01-B