


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established in 1882 by George S. Pershin, under General Land Office Contract No. 430. Surveyor General's records state
Set a basalt stone 17x8x7 ins. 12 ins. in ground on slight South slope for 1/4 Sec. Cor. marked 1/4 on West face. No trees. Raised a mound of stone alongside in line of pits.



P-17

Description of corner evidence found:

Found old circle of stone in N-S and SE fence corner. Found 16"x8"x5" stone, 1/4 visible in fence rock jack 20' South of circle of stone. Due to harmony with surrounding corners, the center of the circle of stone is accpeted as the 1/4 corner position.

No bearing trees established.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 3"x30" galv. iron pipe with 3" brass cap, stamped as shown on the diagram. Set 16" in the ground. Placed original stone North alongside the pipe and raised a mound of stone around the pipe. No bearing trees available. Set steel fence posts with warning and boundary signs 5 ft. East and 5 ft. South from corner.

I hereby certify that the above corner monument was reestablished on 7/28/81 as herein described.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Douglas M. Ferguson
OREGON
JULY 12, 1968
DOUGLAS M. FERGUSON
848

Witnesses: _____
D. Mitchell Ferguson

Dave Herburger

Office of Umatilla Co. Surveyor County of Umatilla
Oregon
State of _____ I hereby certify that the within instrument was filed in this office
for record on the 7th day of January 1981
Douglas M. Ferguson by Betty Skala
(COUNTY OFFICIAL) (DEPUTY)

82-16

T-2