


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Not previously established.



P-19

Description of corner evidence found:

N/A

Description of monument and accessories established to perpetuate the original location of this corner:

Set 3"x30" galv. iron pipe with 3" brass cap stamped as shown in the diagram, set 14" in the ground and raised a mound of stone around the pipe. From which:  
 A pine 24" dia. bears N27°30' E, 20.2 ft. scribed C1/4 S23 BT.  
 No other trees available.  
 Set wood post with location poster and boundary sign 5 ft. south.  
 Set steel post with warning sign and boundary sign 5 ft. East.  
 Nailed bearing tree tag and brass washer stamped PLS 848 to the tree.  
 Painted red band around tree.

I hereby certify that the above corner monument was established on 7/28/81 as herein described.

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

*Douglas M. Ferguson*  
 OREGON  
 JULY 12, 1968  
 DOUGLAS M. FERGUSON  
 848

Witnesses: D. Mitchell Ferguson

Mike Woodward

Office of...County...Surveyor..... County of...Umatilla.....  
 State of...Oregon..... I hereby certify that the within instrument was filed in this office  
 for record on the...27<sup>th</sup>... day of...January..... 1982  
 David A. Sumner..... by Betty Slatta.....  
 (COUNTY OFFICIAL) (DEPUTY)

82-01-B

T-2