


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established in 1882 by George S. Pershin under General Land Office Contract No. 430. Surveyor General's records state:
Set basalt stone 12 x 10 x 8 ins., 8 ins. in ground on E slope for 1/4 Sec. Cor. marked 1/4 on W face.

A pine 5 ins. dia. bears S40°E, 29 lks. dist. marked 1/4 S BT.

A pine 15 ins. dia. brs. N44°W, 50 lks. dist. marked 1/4 S BT.



P-21

Description of corner evidence found:

Found basalt stone 12"x10"x8" set in mound of stone. 1/4 on West face.

No evidence of original bearing trees.

Accepted center of 12"x10"x8" stone as the 1/4 cor. position.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 3"x30" galv. iron pipe with 3" brass cap stamped as shown on the diagram. Set 16" in the ground and raised a mound of stone and earth around the pipe.

From which:

A pine 9" dia. bears N3°W, 35.2 ft. scribed 1/4 S 23 BT.

A pine 10" dia. bears N74°E, 25.9 ft. scribed 1/4 S 24 BT.

Set steel posts with warning and boundary signs 5 ft. North and 5 ft. East from corner. Nailed bearing tree signs and brass washers stamped PLS 848 to each tree.

Painted red band around each tree.

I hereby certify that the above corner monument was reestablished on 7/2/81 as herein described.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Douglas M. Ferguson
OREGON
JULY 12, 1968
DOUGLAS M. FERGUSON
848

Witnesses: D. Mitchell Ferguson

Dave Herburger

Office of Co. Surveyor County of Umatilla
Oregon
I hereby certify that the within instrument was filed in this office
for record on the 25 day of January, 1982
Nancy Baumheim by Betty Shatto
(COUNTY OFFICIAL) (DEPUTY)