


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner not previously established.



P. 22

Description of corner evidence found:

N/A

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 3"x30" galv. iron pipe with 3" brass cap, stamped as shown on the diagram, set 10 in. in the ground and raised a mound of stone around the pipe.

From which:

A pine 10 in. dia. bears N43°W, 24.1 ft. scribed CW 1/16 S 24 BT.

A pine 10 in. dia. bears S 12°E, 26.2 ft. scribed CW 1/16 S 24 BT.

Set steel posts with warning and boundary signs, 5 ft. West and 5 ft. South from corner.

Nailed bearing tree signs and brass washers stamped PLS 848 to each tree. Painted red band around each tree.

I hereby certify that the above corner monument was established on 7/2/81 as herein described.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

[Signature]
OREGON
JULY 12, 1968
DOUGLAS M. FERGUSON
848

Witnesses:

D. Mitchell Ferguson

Dave Herburger

Office of Co. Surveyor County of Umatilla
State of Oregon I hereby certify that the within instrument was filed in this office
for record on the 7th day of January, 1982
David Krumbein by Betty Shatto
(COUNTY OFFICIAL) (DEPUTY)

82-01-B