


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner not previously established.



P-24

Description of corner evidence found:

N/A

Description of monument and accessories | established to perpetuate the original location of this corner:

Set 3"x30" galv. iron pipe with 3" brass cap stamped as shown on the diagram. Set pipe 15 inches in the ground and raised a mound of stone around the pipe.

From which:

A pine 12 inches dia. bears N23°E, 107.4 ft. scribed CE 1/16 S 24 BT.
A pine 12 inches dia. bears S1°W, 41.5 ft. scribed CE 1/16 S 24 BT.
Set steel posts with warning and boundary sign 5 ft. S and 5 ft. East from corner.

Nailed bearing tree signs and brass washers stamped PLS 848 to each tree. Painted red band around each tree.

I hereby certify that the above corner monument was established as herein described, on 8/13/81.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 12, 1968
DOUGLAS M. FERGUSON
848

Witnesses:

D. Mitchell Ferguson

Mike Woodward

Office of... Co. Surveyor..... County of... Umatilla.....

State of... Oregon....., I hereby certify that the within instrument was filed in this office

for record on the... 27th day of... January....., 1982

Douglas M. Ferguson by Betty Thudd

(COUNTY OFFICIAL)

(DEPUTY)

82-01-C

T-2