


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established in 1882 by George S. Pershin under General Land Office Contract No. 430. Surveyor General's notes state:
A pine 8" dia. on North slope for 1/4 sec. cor.
A pine 8" dia. brs. S54°E 22 lks. dist.
A pine 40" dia. brs. S77°W 33 lks. dist.



P-25

Description of corner evidence found:

Found depression in the ground which appears to be where a tree once grew. Found down, dead, rotten pine tree at approximate record call position from depression. Proportion position falls in depression; therefore, accepted as 1/4 corner position.

Description of monument and accessories established to perpetuate the original location of this corner:

Set 3"x30" galv iron pipe with 3" brass cap stamped as shown on the diagram; set 26 inches in the ground. From which:
A fir 11 in. dia. bears N25°E, 12.3 ft. scribed 1/4 S 19 BT.
A pine 12 in. dia. bears S67°W, 5.7 ft. scribed 1/4 S 24 BT.
Set steel posts with warning and boundary signs 5 ft. South and 5 ft. West from corner.
Nailed bearing tree signs and brass washers stamped pLS 848 to each tree. Painted a red band around each tree.

I hereby certify that the above corner was established as herein described on 8/13/81.

Witnesses: D. Mitchell Ferguson

Mike Woodward



Office of Co. Surveyor County of Umatilla
Oregon, I hereby certify that the within instrument was filed in this office for record on the 13th day of JANUARY, 1982
David Krause by Billy Shallo
(COUNTY OFFICIAL) (DEPUTY)

82-01-B