


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner not previously established.



Q-25

Description of corner evidence found:

N/A

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 3"x30" galv. iron pipe with 3" brass cap stamped as shown on the diagram. Set pipe 8 inches in ground and raised a mound of stone around the pipe.

From which:

A pine 16 inches dia. bears S27°E, 60.6 ft. scribed S 1/16 S 19 BT.

A pine 16 inches dia. bears S38°W, 61.5 ft. scribed S 1/16 S 24 BT.

Set steel posts with warning and boundary signs 50ft. North and 5 ft. West from corner.

Nailed bearing tree signs and brass washers stamped PLS 848 to each tree.

Painted red band around each tree.

I hereby certify that the above corner monument was established as herein described, on 8/13/81.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*[Signature]*  
OREGON  
JULY 12, 1968  
DOUGLAS M. FERGUSON  
848

Witnesses: D. Mitchell Ferguson

Mike Woodward

Office of Col Surveyor Umatilla County of Oregon  
State of Oregon, I hereby certify that the within instrument was filed in this office  
for record on the 7<sup>th</sup> day of January, 1982  
David K. Anderson by Betty Thada  
(COUNTY OFFICIAL) (DEPUTY)