


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

S.
Corner established in 1882 by George Pershin
under General Land Office Contract No. 430.
Surveyor General's records state:
Set basalt stone 18x12x10 in mound of stone
on SW slope for 1/4 Sec. Cor. No trees.



T-25

Description of corner evidence found:

Corner has been destroyed by fence construction.
No bearing trees previously established.
Positioned corner by proportion from found corners
1/2 mile North and 1/2 mile South.

Description of monument and accessories I established to perpetuate the
original location of this corner:

Set 3"x30" galv. iron pipe with 3" brass cap stamped as shown on the
diagram; set 10 inches in the ground and raised a mound of stone
around the pipe.

No bearing trees available.

Set steel posts with warning and boundary signs 7.0 ft. North
and 6.2 ft. West from corner.

I hereby certify that the above corner
monument was reestablished as herein
described on 7/29/81.

Witnesses:

D. Mitchell Ferguson

Mike Woodward



Office of..... Co. Surveyor..... County of..... Umatilla.....
State of..... Oregon..... I hereby certify that the within instrument was filed in this office
for record on the..... 7th day of..... January....., 1982
..... David Kraus Green..... by Betty Stahl.....
(COUNTY OFFICIAL) (DEPUTY)