

USDA-FOREST SERVICE

Index File No. U-24

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. \_\_\_\_\_ Cor. No. \_\_\_\_\_

T 45 R. 30E R.D. Ukiah County Umatilla  
 Merid. Willamette N.F. Umatilla State Oregon

CORNER DIAGRAM

T45 R30E  
 SE 1/16 S 25  
 1981  
 PLS 848



DESCRIBE CORNER MONUMENT FOUND

Corner not previously established.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

N/A

PHOTO IDENTIFICATION DATA

Photo No. \_\_\_\_\_  
 Filed At. \_\_\_\_\_  
 Object Ident. \_\_\_\_\_  
 Ident. By \_\_\_\_\_  
*Signature*

PLANE COORDINATE POSITION DATA

State \_\_\_\_\_ Zone \_\_\_\_\_  
 X \_\_\_\_\_  
 Y \_\_\_\_\_  
 Estab. By \_\_\_\_\_  
*Agency*

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner is on brushy NE slope approx.  
 200 ft. SW from draw bottom.

*[Signature]*  
 Signature

Title \_\_\_\_\_ Division \_\_\_\_\_ Headquarters \_\_\_\_\_ Date \_\_\_\_\_  
 PLS 848 Mt. Vernon, OR 7/29/81

1

2

3

6

7

8

4

5

7100-52-(3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set 3"x30" galv. iron pipe with 3" brass cap stamped as shown on the diagram. Set pipe 24 inches in the ground.

From which:

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE.

A lodge pole pine 9 in. dia. bears N1°E, 30.6 ft. scribed SE 1/16 S25 BT  
A fir 8 in. dia. bears S11°E, 8.2 ft. scribed SE 1/16 S 25 BT.  
Set steel posts with warning and boundary signs 5 ft. South and 5 ft. East from corner.  
Nailed bearing tree signs and brass washers stamped PLS 848 to each tree  
Painted red band around each tree.

Work Done By D.M. Ferguson Title Surveyor Date 7/29/81 State Registration No. or Agency ORPLS 848

Certified Cor. Record Prepared? Yes  No  Filed At: Umatilla Co. Surveyor Off Date

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

REMARKS

Witnesses to above corner:  
D. Mitchell Ferguson  
Mike Woodward

OREGON  
JULY 12, 1968  
DOUGLAS M. FERGUSON  
848