


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: Corner established in 1882 by George S. Pershin under General Land Office Contract No. 430.

Surveyor General Record States:

Set basalt stone 16 x 10 x 4 ins. in mound of stone for cor. to sect's 33-34-3-4-marked with 3 notches on East & West edges. From which:

- A 10" Pine bears N 38 E, 126 lks.
- A 9" Pine bears S 39 E, 47 lks.
- A 24" Pine bears S 37 W, 15 lks.
- A 22" Pine bears N 45 W, 18 lks.



z-13

No record of subsequent remonumentation was found in County Records.

Description of corner evidence found:

Found original stone, call size, properly marked in a mound of stone, from which:

Original BTs

- A 18" Pine, good condition, bears N41E, 86.6 ft., blaze healed.
- A 18" Pine, good condition, bears S41E, 36.1 ft., scribes visible.
- A 30" Pine stump bears S25W, 12.2 ft., scribes visible.
- A 28" Pine, good condition, bears N41W, 12.6 ft., scribes visible.


Description of monument and accessories established to perpetuate the original location of this corner

In place of stone, set 2 1/2"x30" iron pipe with brass cap marked as shown, 28" in ground, from which:

New BT

A 20" Pine bears S33W, 48.7 ft. marked T5S R30E S4 BT.

Nailed brass washer to BT blaze.
Buried original stone South and along side pipe.
Set steel fence post 5+ ft. North of corner.
Used steel tape and magnetic compass with 20° E declination.
Measured to face of blaze on original BTs and center of new BT.



Office of Surveyor County of Washtenaw
 State of Michigan, I hereby certify that the within instrument was filed in this office
 for record on the 13 day of August, 1974, at o'clock m., (signed)
Ralph J. Thompson by (DEPUTY)

I-110-R