


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

A-20

History of original corner establishment:

None.

No record of corner establishment appears in County Records.



Description of corner evidence found:

None.

Description of monument and accessories I established to perpetuate the original location of this corner:

I set 2 1/2" brass cap on 2 1/2" x 30" l. pipe 12" in ground with mound of stone from which:

A 16" dia Ponderosa Pine bears S43°W 33.7 ft dist marked: E 1/16 S2 BT.

A 19" dia Ponderosa Pine bears S43°E 79.5 ft dist marked: E 1/16 S2 BT.

Blaze faces and 6" band around bearing trees are painted red. Tagged trees with 54-3 & 9 signs.

New BTs have lower blaze, scribed BT, with a brass washer stamped PLS 1106 nailed flush.

Set Steel fence post with 54-2 & 9 sign attached, West of corner.

Used steel tape and magnetic compass 19 3/4° East declination. Measured to center of BTs.

Corner monumented on October 20, 1982.

Cap marked:

Witnessed by: Leslie E. Wilson

**REGISTERED  
PROFESSIONAL  
LAND SURVEYOR**

*William R. Wells*

OREGON  
JULY 22, 1977  
**WILLIAM R. WELLS**  
1106

S34  
T3S R31E  
E 1/16 S2  
T4S R31E  
1982  
PLS 1106

Office of... County Surveyor..... County of... Umatilla  
State of... Oregon....., I hereby certify that the within instrument was filed in this office  
for record on the 15<sup>th</sup> day of December, 1982  
David H. Krumbein by Betty L. Shatto  
(COUNTY OFFICIAL) (DEPUTY)

A-20

Form R6-7100-57 (9/71)

**RECEIVED BY**  
**Umatilla County Surveyor**  
Date \_\_\_\_\_  
Rec'd -y \_\_\_\_\_  
No. 82-138-B