

USDA-FOREST SERVICE

Index

File No.

A-20

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or

Survey No.

Sec 2

Cor.

No. E 1/16

T 4S R. 31E

R.D. Ukiah

County Umatilla

Merid. Willamette

N.F. Umatilla

State Oregon

CORNER DIAGRAM

~~S34~~

T3S R31E

E 1/16 S2

T4S R31E

N

DESCRIBE CORNER MONUMENT FOUND

None.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None.

PHOTO IDENTIFICATION DATA

Photo No. _____

Filed At. _____

Object Ident. _____

Ident. By _____

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Road #5420 to road #5412-100, then West on road #5412-100 approx. 1.4 miles to fork South through gate, then West across meadow and South at fork approx. 0.5 miles from gate, then South to end of road @ S 1/4 S34 on East side of road and E 1/16 S2 on West edge of road end. Near fence corner in sparce timber.

Signature

Willie R. Wells

Title

PLS 1106

Division

Headquarters

Date

October 20, 1982

7100-52-(3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set 2 1/2" brass cap on 2 1/2" x 30" l. pipe 12" in ground with mound of stone.

Set steel fence post with 54-2 & 9 signs attached, West of corner. Cap marked:

~~534~~
T3S R31E
E 1/16 S2
T4S R31E
1982
PLS 1106

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A 16" dia Pond. Pine bears S43°W 33.7 ft dist marked: E 1/16 S2 BT.

A 19" dia Pond. Pine bears S43°E 79.5 ft dist marked: E 1/16 S2 BT.

Blaze faces and 6" bands around bearing trees are painted red. Trees tagged with 54-3 & 9 signs. Each new BT has lower blaze, scribed BT, with brass washer stamped PLS 1106 nailed flush.

Work Done By W.R. Wells Title Surveyor Date 10/20/82 State Registration No. PLS 1106
For Agency

Certified Cor. Record Prepared? Yes No Filed At: Umalla County Surveyor Office Date

REMARKS

Witnessed by: Leslie E. Wilson