

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

P - 5
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on October 29, 1880, under GLO contract No. 373, as follows:

Set a basalt stone, 18" x 12" x 7", on an east slope for the 1/4 section corner, from which:

- A 40" pine bears N14° E, 57 links (37.62 feet).
- A 28" pine bears N30° W, 151 links (99.66 feet).

Corner evidence recovered:

Found the original corner stone solidly set in a mound of stones. The corner stone is 20" x 12" x 6" and is marked "1/4" on the west face, from which:

- A sawn and decayed 40" Ponderosa Pine stump with scribes, "BT", visible, bears N14° E, 37.62 feet to the scribed face.
- A 41" live and vigorous Ponderosa Pine with double headed blazes bears N30° W, 99.66 feet to the location of the original blazed face. I place a "Bearing Object" sign on this tree above the blazes.

Monument and accessories established to perpetuate the original position of this corner:

In place of the corner stone, I set a 1" x 30" galvanized iron pipe 12" into the ground to bedrock. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above. I bury the corner stone to the southeast of the pipe and build a mound of stones around the pipe, from which:

- A 13" Ponderosa Pine, scribed "1/4 S20 BT", bears N28° E, 40.9 feet.
- A 11" Ponderosa Pine, scribed "1/4 S20 BT", bears S42° 30' E, 69.4 feet.
- A 8" Ponderosa Pine, scribed "1/4 S19 BT", bears S30° W, 92.6 feet.

The three new bearing trees are scribed on double blazes and have a 3/4" brass washer, marked "PLS 1636", nailed flush to the base of the lower blaze.

I hereby certify the above corner point was perpetuated as hereon described on June 21, 2001. Magnetic declination set in compass: 18°E.


Dennis L. Gaylord


Renews June 30, 2003

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, _____, 2001.

RECEIVED BY
 Umatilla County Surveyor
 Date 6-01
 Rec'd By KK
 No. 01-93-R