

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 12/2/95

CORNER DESIGNATION: R-21. Southeast corner, Section 23, T4S., R31E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Most recent approved GLO Survey was made by George S. Pershin, under Contract dated September 17, 1880. Record states: Set Pine post on level for Cor. to Secs. 23, 24, 25 & 26.

- A Pine 4 ins. diam. brs. N. 67° E. 10 lks. dist.
- A Pine 24 ins. diam. brs. S. 28° E. 76 lks. dist.
- A Pine 20 ins. diam. brs. S. 27° W. 78 lks. dist.
- A Pine 18 ins. diam. brs. N. 85° W. 65 lks. dist.

MONUMENT AND ACCESSORIES FOUND: A 2 foot diameter mound of stones from which:

A down 24" ponderosa pine snag with scribes visible on double blaze bears S 28° E, 50.2 feet to root hole, (original bearing tree).

A down 28" ponderosa pine snag bears S 27° W, 51.5 feet to root hole, scribes are on down side of tree, (original bearing tree).

A 22" down ponderosa pine snag bears N 85° W, 42.9 feet to root hole with visible scribes, (original bearing tree).

MONUMENT MARKING DETAIL:

```

T4S      R31E
S23 | S24
---|---
S26 | S25
    1995
PLS 1715

```

MONUMENT SET: At center of found stone mound: Set a 1 1/4" x 30" galvanized iron pipe with a 2 1/2" brass cap, 22" in the ground and surrounded with a mound of earth and stone (marked as shown in monument detail).

New Accessories:

A 12" ponderosa pine bears N 69 1/2° E, 31.6 feet, scribed T4S R31E S24BT.

A 10" ponderosa pine bears S 29° E, 38.4 feet, scribed T4S R31E S25BT.

An 11" ponderosa pine bears S 51° W, 20.0 feet, scribed T4S R31E S26BT.

A 4" ponderosa pine bears N 40 1/2° W, 45.9 feet, scribed "X" at breast height and "BT" at base.

Attached "Bearing Object" signs to original and new bearing trees.

LOCATION & COMMENTS:

COMPASS DECLINATION: 18° East.

Surveyor's Seal

Party Chief: Gary Burnett, PLS

Notes: William R. Wells, PLS RECEIVED BY

Umatilla County Surveyor

Date 12-95

Rec'd By KE

No. 95-216-R



Expires 12/31/97