

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

R - 9
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on October 27, 1880, under GLO contract No. 373, as follows:

T4S R31E
S20|S21
S29|S28
PLS 1636
1998

Set a basalt stone 20" x 10" x 8" in a sag in a point of timber on a slight northeast slope for the corner to sections 20, 21, 28 and 29, from which:
A 12" pine bears N86°E, 30 links (19.80 feet).
A 14" pine bears S46°E, 84 links (55.44 feet).
A 11" pine bears S34°W, 172 links (113.52 feet).
A 10" pine bears N66°W, 84 links (55.44 feet).

Corner evidence recovered:

Found the original corner stone out of place about 10 feet southeast. The corner stone is 20" x 11" x 9" and is plainly marked with 4 notches on one edge and 4 notches on another. From the corner point as determined by reference to the original bearing trees:
A 38" Ponderosa Pine with scribes partly visible on a nearly healed blaze bears N85°E, 19.8 feet.
A sawn and decayed Ponderosa Pine stump with no remaining marks bears S42°30'E, 55.4 feet.
A sawn and decayed Ponderosa Pine stump with axe marks under 8" of healed wood bears S34°W, 113.5 feet.
A sawn and decayed Ponderosa Pine stump with scribe, "T", visible bears N65°W, 55.4 feet.
The corner point is on the east edge of a mound of stones. Distance measurements are to the scribed face of the original bearing trees.

Monument and accessories established to perpetuate the original location of this corner:

At the corner point as determined by reference to the original bearing trees, I set a 1" x 30" iron pipe 24" into the ground. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above. I bury the original corner stone along the northeast side of the pipe and build a mound of stones around the pipe to the cap, from which:
A 17" Ponderosa Pine scribed "T4S R31E S28 BT" bears S11°30'E, 58.2 feet.
A 14" Ponderosa Pine scribed "T4S R31E S29 BT" bears S45°W, 32.0 feet.
A 19" Ponderosa Pine scribed "T4S R31E S20 BT" bears N60°W, 136.6 feet.
This bearing tree is north of a small draw.
The original living bearing tree and the three new bearing trees each have a "Bearing Object" sign nailed above the blazes and a "Witness Point" sign nailed to the back of the tree. The original bearing tree stumps to the southwest and northwest have "Bearing Object" signs nailed to them. The original bearing tree stump to the southeast is too decayed to hold a sign. The three new bearing trees are scribed on double blazes and have a 3/4" brass washer, marked "PLS 1636" nailed flush to the scribed "B". This corner is about 50 feet south of a small draw flowing easterly.

I hereby certify the above corner point was perpetuated as hereon described on August 16, 1998. Magnetic declination: 18°E.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Dennis L. Gaylord

OREGON
JULY 31, 1973
DENNIS L. GAYLORD

Renews June 30, 1999

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on _____, 1998

RECEIVED BY

Umatilla County Surveyor

Date 9-28

Rec'd By AK

No. 98-183-R