

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T - 5  
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on October 28, 1880, under GLO contract No. 373, as follows:

T4S R31E  
1/4  
S30|S29  
PLS 1636  
1998

Set a basalt stone 15" x 12" x 4" in a mound of stones on a northeast slope for the 1/4 section corner, from which:

A 8" pine bears S86°E, 174 links (114.84 feet).

Corner evidence recovered:

Found the original corner stone solidly set in a mound of stones. The corner stone is 15" x 12" x 5" and is plainly marked "1/4" on the west face, from which:

The original 8" pine is a dead and down 24" Ponderosa Pine. I open and find scribes "1/4S". The broken stump bears S86°E, 111.6 feet, which is five links less distance than the record, above.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" iron pipe 13" into the ground to bedrock. A 2 1/2" brass cap attached is marked as shown in the diagram above. I bury the corner stone to the south of the pipe and build a mound of stones around the pipe to the cap, from which:

- A 13" Ponderosa Pine scribed "1/4 S29 BT" bears N36°E, 87.8 feet.
- A 11" Ponderosa Pine scribed "1/4 S29 BT" bears S70°30'E, 88.6 feet.
- A 7" Ponderosa Pine scribed "1/4 S30 BT" bears S32°W, 71.4 feet.
- A 8" Ponderosa Pine scribed "1/4 S30 BT" bears N48°15'W, 72.2 feet.

The four new bearing trees are scribed on double blazes, have a 3/4" brass washer, marked "PLS 1636", nailed flush to the scribed "B", have a "Bearing Object" sign nailed above the blazes and have a "Witness Point" sign nailed to the back. The original 24" down and dead bearing tree has a "Bearing Object" sign nailed to it.

I hereby certify the above corner point was perpetuated as hereon described on August 6, 1998. Magnetic declination: 18°E.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Dennis L. Gaylord*

OREGON  
JULY 14, 1978  
DENNIS L. GAYLORD  
1636

Renews June 30, 1999

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on \_\_\_\_\_, 1998.

RECEIVED BY

Umatilla County Surveyor

Date 9-98

Rec'd By KK

No. 98-184-R