


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

V - 5
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on October 28, 1880, under GLO contract No. 373, as follows:



Set a basalt stone, 14" x 12" x 10", and a post in a mound of stones on an east slope for the corner to sections 29, 30, 31 and 32.

Corner Evidence Recovered:

Found the original corner stone solidly set on the northeast edge of a mound of stones. The corner stone is 15" x 13" x 7" and is plainly marked with 4 notches on the east edge and with at least 4 notches on the north edge. The original post is gone.

Monument and accessories established to perpetuate the original location of this corner:

In place of the original corner stone, I set a 1" x 30" iron pipe 25" into the ground. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above. I bury the corner stone along the east side of the pipe and build a mound of stones around the pipe to the cap, from which:

A 5/8" x 24" iron rod set 20" into the ground with a 3/4" brass washer, marked "PLS 1636 29", attached at ground level bears N46°30'E, 160.1 feet.

A 7" Ponderosa Pine scribed "S32 BT" on double blazes bears S10°30'E, 236.9 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 31", attached at ground level bears S46°45'W, 99.1 feet.

A 5/8" x 24" iron rod set 21" into the ground with a 3/4" brass washer, marked "PLS 1636 30", attached at ground level bears N35°30'W, 159.8 feet.

The bearing tree has a 3/4" brass washer marked "PLS 1636 32" nailed flush to the scribed "B" and has a "Bearing Object" sign nailed above the blazes and a "Witness Point" sign nailed to the back.

I hereby certify the above corner point was perpetuated as hereon described on August 16, 1998. Magnetic declination: 18°E.

REGISTERED
PROFESSIONAL
LAND SURVEYOR
Dennis L. Gaylord
OREGON
JULY 14 1973
DENNIS L. GAYLORD
1636
Renews June 30, 1999

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on _____, 1998.

RECEIVED BY
Umatilla County Surveyor
Date 9-98
Rec'd By KR
No. 98-185-Rc