

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

X - 9
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on October 27, 1880, under GLO contract No. 373, as follows:

T4S R31E
1/4
S32|S33
PLS 1636
1998

Set a basalt stone 17" x 13" x 5" on northeast slope for 1/4 section corner, from which:

- A 8" fir bears N18°E, 47 links (31.02 feet).
- A 8" fir bears N80°W, 28 links (18.48 feet).

Corner evidence recovered:

Found the original corner stone solidly set on the north edge of a mound of stones. The corner stone is 19" x 13" x 6" and is plainly marked "1/4", from which:

The original 8" fir is now a 27" Douglas-fir with double healed blazes which bears N76°W, 20.3 feet (19.0 feet to face). A root hole is all that remains at the location of the original 8" fir to the NE.

Monument and accessories established to perpetuate the original location of this corner:

In place of the original corner stone, I set a 1" x 30" iron pipe 27" into the ground. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above. I bury the corner stone along the north side of the pipe and build a mound of stones around the pipe to the cap, from which:

- A 16" Douglas-fir scribed "1/4 S33 BT" bears N41°E, 21.9 feet.
- A 34" Ponderosa Pine scribed "1/4 S33 BT" bears S67°30'E, 70.6 feet.
- A 19" Douglas-fir scribed "1/4 S32 BT" bears S36°W, 29.5 feet.

The three new bearing trees are scribed on double blazes, and have a 3/4" brass washer, marked "PLS 1636", nailed flush to the scribed "B". All four bearing trees have a "Bearing Object" sign nailed above the blazes and a "Witness Post" sign nailed to the back of the tree. A fence corner with barbed-wire fences projecting north and west, bears N26 E, 103 feet.

I hereby certify the above corner point was perpetuated as hereon described on July 9, 1998. Magnetic declination: 18°E.



Renews June 30, 1999

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on _____, 1998.

RECEIVED BY
 Umatilla County Surveyor
 Date 8-98
 Rec'd By JK
 No. 98-1638