


USDA-FOREST SERVICE

Index
 File No. C-5
 T 4S R. 32E
 Merid. W.M.

CORNER RECORD (SEARCH) (Ref. FSM 7151.4)
 Tract or Survey No. _____ Cor. No. 1/4
 R.D. Ukiah County Umatilla
 N.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

Found 15"x12"x4" basalt stone marked 1/4 on west face.
 Firmly set from which:

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

Dead fir 21" in dia. bears N85°W, 22.0 feet. Opened tree and found some scribing. Dead fir 35" in dia. bears S85°E 16.0 feet. Too rotten to read scribing. (Fell over by 11/28/77)

PHOTO IDENTIFICATION DATA

Photo No. _____
 Filed At. _____
 Object Ident. _____
 Ident. By _____
 Signature _____

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner is about 250' south of main road through Granite Meadows.

PLANE COORDINATE POSITION DATA

State _____ Zone _____
 X _____
 Y _____
 Estab. By _____
 Agency _____

Signature Barney B. Barbour P.L.S. Division _____ Headquarters _____ Date 11/3/77 7100-52 (3/68)

CORNER RECORD (PERPETUATION)

GPO 902-673

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

At corner point set 2½"x30" galvanized pipe with brass cap marked:
Set pipe 22" in the ground with mound of stone around. Placed
marked stone at base of pipe.

T4S R32E
1/4
S6 + S5
OR PLS 1051
1977

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A pine 25" in dia. bears N70°W, 73.5', scribed 1/4 S6 BT. A pine 16" in dia. bears
S01° E, 55.3' scribed 1/4 S5 BT. Placed 54-3s on all the BT's, 54-4s on new BT's,
Placed brass washer stamped PLS 1051 on BT blazes. Placed 54-4 on fence post 3'
west of corner. Painted 6" red bands and both blazes red.

Work Done By B.B. Barbour Title P.L.S. Date 11/9/77 State Registration No. OR PLS 1051
or Agency

Certified Cor. Record Prepared? Yes No Filed At _____ Date _____

REMARKS

Above corner witnessed by D.L. Landers, S. Nelson.

Index File No. _____ T. _____

R. _____

M. _____

Tract or Surv. No. _____

Cor. _____

12

13