

USDA-FOREST SERVICE

Index  
File No. K-7  
T 4S R. 32E  
Merid. W.M.


CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or  
Survey No. \_\_\_\_\_ Cor. No. CN1/16

R.D. Ukiah County Umatilla  
N.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

None set.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None set.

PHOTO IDENTIFICATION DATA

Photo No. \_\_\_\_\_  
Filed At. \_\_\_\_\_  
Object Ident. \_\_\_\_\_  
Ident. By \_\_\_\_\_

*Signature*

PLANE COORDINATE POSITION DATA

State \_\_\_\_\_ Zone \_\_\_\_\_  
X \_\_\_\_\_  
Y \_\_\_\_\_  
Estab. By \_\_\_\_\_

*Agency*

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner falls about 100 feet east of a track road and 20 feet south and west of a fence corner.

*Signature*

*Barry B Barbour*

Title  
*P, L, S.*

Division

Headquarters

Date

*11/3/77*

7100-52-(3/68)

**CORNER RECORD (PERPETUATION)**

GPO 902-673

**MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT**

Set 2½"x30" galvanized pipe with brass cap marked:

Set pipe 6" in the ground to bedrock and mound of stone around to cap.

T4S      R32E  
 NI/16    C      S17  
           |  
           C  
 OR PLS 1051  
 1977

**ACCESSORIES: DESCRIBE NEW BT'S, WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE**

From which: A pine 16" in dia. bears N50°E, 12.8' scribed N1/16 S17 BT. A pine 14" in dia. bears S82°W, 58.8' scribed N1/16 S17 BT. Placed 54-3s, and 54-4s and brass washers stamped PLS 1051 on BT blazes. Painted blazes red and 6" red band around BT's. Placed 54-2 and 54-4 on fence post 6' each of corner. Placed 54-2 and 54-9 on fence post 5' south of corner.

Work Done By B.B. Barbour Title P.L.S. Date 11/3/77 State Registration No. OR PLS 1051  
 or Agency

Certified Cor. Record Prepared? Yes  No  Filed At: \_\_\_\_\_ Date \_\_\_\_\_

**REMARKS**

Witnesses to the above: D.L. Landers, S. Nelson