

Index
File No. L-13

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. _____ Cor. No. _____


T 4 S R. 32 E

R.D. Ukiah County Umatilla

Merid. Willamette

N.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

Found 2 1/2" iron pipe with 3 1/4" brass cap (as shown in corner diagram) no stones available.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

- A 12" douglas fir brs S69°W, 8.2' with scribing visible.
- A 30" douglas fir brs N74 1/2°E, 19.7' with scribing visible.
- A 18" douglas fir dead top brs N71 1/2°E, 66.7' with scribing visible.

PHOTO IDENTIFICATION DATA

Photo No. _____
Filed At. _____
Object Ident. _____
Ident. By _____
Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner falls on Westerly slope about 7' West of N-S fence, posted line N & S.

PLANE COORDINATE POSITION DATA

State _____ Zone _____
X _____
Y _____
Estab. By _____
Agency

Signature

Walter R. Wells

Title

Land Surveyor

Division

Headquarters

Pendleton, Ore.

Date

6-03-92

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set steel fence post next to corner with sign 54-9 & 54-2 attached.
Compass declination 18° East.

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

New bearing trees established:

A. 10" ponderosa pine brs N52 $\frac{1}{4}$ ° E, 50.9' scribed 1/4S15 BT.

A. 15" ponderosa pine brs S82 $\frac{1}{2}$ ° E, 74.0' scribed 1/4S15 BT.

A. 17" ponderosa pine brs S21° E, 32.8' scribed 1/4S15 BT.

New BT's have a brass washer stamped PLS 1106 nailed to face of blaze.

Attached sign 54-3 & 54-9, painted face of blaze & a 6" red band around each BT.

Work Done By W.R. Wells Title Land Surveyor Date 6-03-92 State Registration No. ORLS 1106
or Agency

Certified Cor. Record Prepared ? Yes Filed At: Umatilla County Surveyor Date 7-92

REMARKS

Index File No.

L-13

T. 4 S R. 32 E

WM.

Tract or Surv. No.

Cor.