

USDA FOREST SERVICE

CORNER RECORD (SEARCH)

Index

File No. N-19

R.D.: N.F.J.D.

Co. Survey No:

T.4S., R.32E.

N.F.: UMATILLA

County: Umatilla

Meridian: Willamette

| | | |
|----------------|--|--|
| CORNER DIAGRAM | | DESCRIBE CORNER MONUMENT FOUND |
| T4S R32E | | Found an iron monument, extending approx. 6" from the |
| S14 | | ground, with a brass cap marked as shown in diagram. The |
| 1/4 | | monument is solid and in good shape. |
| S23 | | |
| 1977 | | |
| (BLM Cap) | | DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND |
| PHOTO ID DATA | | White Fir snag, 28" dia., with scribing visible, bears |
| Photo No. | | S37°12'W, 30.6 ft. This is the original BT. (Rec: S40°W, |
| Filed At | | 31.02 ft.) |
| Object ID | | White Fir snag, 16" dia., with scribing visible, bears |
| PLANE CO-ORD | | N53°36'E, 36.9 ft. (BLM Rec: N54°E, 37.95 ft.) |
| State Zone | | |
| X | | |
| Y | | DESCRIBE CORNER LOCATION: |
| Estab.By | | Corner falls in the center of a N-S streambed. |

Signature



Title: Land Surveyor

Date: 10/17/94

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MON.
No work is needed on the monument.
From Which:

ACCESSORIES: DESCRIBE NEW BT'S, W.O.'S ETC. ESTABL./WORK DONE TO PRESERVE
Western Larch, 12" dia., bears N75°00'W, 53.3 ft., scribed: 1/4 S14 BT
Spruce, 24" dia., bears N85°45'E, 68.9 ft., scribed: 1/4 S14 BT
Douglas Fir, 16" dia., bears S61°15'E, 27.4 ft., scribed: 1/4 S23 BT
Western Larch, 20" dia., bears S80°15'W, 80.3 ft., scribed: 1/4 S23 BT
Measurements to BT's taken with a magnetic compass, declination 20° East,
and a nylon clad steel tape. Set steel fence post with Land Survey
Monument (54-9) and Property Boundary (54-2) signs 5' east and west of the
monument. Nailed a brass washer stamped PLS 2405 on blaze above BT scribe
as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and
Land Survey Monument (54-9) signs on back of each tree as required.
Painted a 6" red band above Bearing Trees signs.

Work Done by: Susan E. Newstetter Or. Land Surveyor No. 2405 Date: 10/17/94
Certified Cor. Record Prepared? Yes No Filed At: Umatilla Co. Survey.

REMARKS

Index File No. N-19

T.4S., R.32E., W.M.