


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

O-13

History of original corner establishment:

None. Corners established as part of this survey.



Description of corner evidence found:

Found a rock mound bearing S08°W, 7½' from corner point with Kinzua location tag referencing it.

Description of monument and accessories established to perpetuate the original location of this corner:

At position established by survey...

Set a 2½"x30" aluminum pipe with 2½" aluminum cap 22" in ground surrounded with mound of earth and stone. Set steel fence post South of corner and attached signs 54-2 & 54-9. Cap marked as shown in corner diagram.

New bearing trees established:

A 8" ponderosa pine brs N21°E, 69.8' scribed N1/16S22 BT.

A 17" ponderosa pine brs N17½°W, 108.9' scribed N1/16S21 BT.

New BT's have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 & 54-9, painted face of blaze & a 6" red band around each BT.

Compass declination 18° East.

I hereby certify that the above corner monument was properly established to U.S.F.S. standards by me on June 05, 1992.

REGISTERED PROFESSIONAL LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of...County...Surveyor..... County of...Umatilla.....

State of...Oregon....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

..... by (DEPUTY)

(COUNTY OFFICIAL)

O-13

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor

Date 7-97

Rec'd By RL

No. 92-50-B

★GPO—799-276