

USDA FOREST SERVICE
Index

CORNER RECORD (SEARCH)

File No. 0-20

R.D.: N.F.J.D.

Co. Survey No:

T.4S., R.32E.

N.F.: UMATILLA

County: Umatilla

Meridian: Willamette

CORNER DIAGRAM | DESCRIBE CORNER MONUMENT FOUND

T4S R32E

NE 1/16

None. Corner established this survey

S23

1994

PLS 2405

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None. Corner established this survey.

PHOTO ID DATA

Photo No.

Filed At

Object ID

PLANE CO-ORD

State Zone

X


Y

Estab. By

DESCRIBE CORNER LOCATION:

Corner falls on flat of scattered P.Pine at top of N-S
draw. An old road is 150 ft. east

Signature:



Title: Land Surveyor

Date: 10/17/94

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MON.
Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown
on the DIAGRAM, 24" in the ground.

From Which:

ACCESSORIES: DESCRIBE NEW BT'S, W.O.'S ETC. ESTABL./WORK DONE TO PRESERVE
Ponderosa Pine, 12" dia., bears S36°45'W, 28.1 ft., scribed: NE 1/16 S23 BT
Ponderosa Pine, 11" dia., bears N04°30'E, 19.5 ft., scribed: NE 1/16 S23 BT
Measurements to BT's taken with a magnetic compass, declination 20° East,
and a nylon clad steel tape. Set steel fence post with Land Survey
Monument (54-9) and Property Boundary (54-2) signs 5' east of the monument
and a steel post 5' south with Property Boundary (54-2) sign. Nailed a
brass washer stamped PLS 2405 on blaze above BT scribe as taken this
survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey
Monument (54-9) signs on back of each tree as required. Painted a 6" red
band above Bearing Trees signs.

Work Done by: Susan E. Newstetter Dr. Land Surveyor No. 2405 Date: 10/17/94
Certified Cor. Record Prepared? Yes No Filed At: Umatilla Co. Survey.

REMARKS

Index File No. 0-20

T.4S., R.32E., W.M.