

USDA FOREST SERVICE
Index

CORNER RECORD (SEARCH)

File No. P-18
T.48., R.32E.
Meridian: Willamette

R.D.: N.F.J.D.
N.F.: UMATILLA

Co. Survey No:
County: Umatilla

CORNER DIAGRAM | DESCRIBE CORNER MONUMENT FOUND

T48 R32E |

W1/16 |

C-----C |

823 |

1994 |

PLS 2405 |

None. Corner established this survey.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None. Corner established this survey.

PHOTO ID DATA |

Photo No. |

Filed At |

Object ID |

PLANE CO-ORD |

State Zone |

X |

Y |

Estab.By |

DESCRIBE CORNER LOCATION:

Corner falls on west slope of P.Pine and D.Fir. An E-W
fence is 35 ft. north.

Signature: *Jue Newletter*

Title: Land Surveyor

Date: 11/3/94

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MON.
Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown
on the DIAGRAM, 12" in the ground and raised a mound of stone and earth
3 1/2 ft. dia. x 1 1/2 ft. high. From which:

ACCESSORIES: DESCRIBE NEW BT'S, W.O.'S ETC. ESTABL./WORK DONE TO PRESERVE
Ponderosa Pine, 8" dia., bears N59°36'W, 53.6 ft., scribed: C-W1/16 S23 BT
Ponderosa Pine, 8" dia., bears S89°24'E, 13.2 ft., scribed: C-W1/16 S23 BT
Measurements to BT's taken with an Electronic Tacheometer with bearings
based on the survey control network. Set steel fence post with Land Survey
Monument (54-9) and Property Boundary (54-2) signs 5' south and east of the
monument. Nailed a brass washer stamped PLS 2405 on blaze above BT scribe
as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and
Land Survey Monument (54-9) signs on back of each tree as required.
Painted a 6" red band above Bearing Trees signs.

Work Done by: Susan E. Newstetter Dr. Land Surveyor No. 2405 Date: 11/3/94
Certified Cor. Record Prepared? Yes No Filed At: Umatilla Co. Survey.

REMARKS

Index File No. P-18

T.4S., R.32E., W.M.