

INDEX No. P-19

History of original corner establishment:

None. Corner established this survey.

DIAGRAM
T4S R32E
C1/4
•
S23
1994
PLS 2405

Description of Corner Evidence Found:

None. Corner established this survey.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the DIAGRAM, 12" in the ground and raised a mound of stone and earth, 3 ft. dia. x 1 ft. high.

From Which:

- Ponderosa Pine, 14" dia., bears N65°02'W, 19.7 ft., scribed: C1/4 S23 BT
- Ponderosa Pine, 12" dia., bears N79°53'E, 7.8 ft., scribed: C1/4 S23 BT
- Ponderosa Pine, 8" dia., bears S27°08'E, 35.5 ft., scribed: C1/4 S23 BT
- Ponderosa Pine, 8" dia., bears S68°15'W, 12.4 ft., scribed: C1/4 S23 BT

Measurements to BT's taken with an Electronic Tacheometer with bearings based on the survey control network. Set steel fence post with Land Survey Monument (54-9) and Property Boundary (54-2) signs 5' south and west of the monument. Nailed a brass washer stamped PLS 2405 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs.

REGISTERED PROFESSIONAL LAND SURVEYOR
Susan E. Newstetter
 OREGON JULY 28, 1989
 SUSAN E. NEWSTETTER 2405
 Renewal Date: 12/31/96

This work was performed by:
Susan E. Newstetter PLS 2405
Witnessed by: Rick Saul and Rick Pewonka
November 2, 1994

RECEIVED BY
 Umatilla County Surveyor
 Date 1-95
 Rec'd By RK
 No. 95-15-B

Office of _____ County of _____
 State of _____ I hereby certify that the within instrument was
 filed in this office for record on the _____ day of _____, 19____
 _____ by _____
 (COUNTY OFFICIAL) (DEPUTY)

P-19