

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. P-21

History of original corner establishment:

This corner was originally established George Pershin, in 1881, under GLO Contract No. 390. Surveyor General Field Notes state:

DIAGRAM  
T4S R32E  
1/4  
S23|S24  
1977

Set basalt stone 14x12x5 in land for 1/4 sec.cor.

(BLM Cap)

A pine 18 ins. diam. brs. N18°E, 69 lks. dist.  
A pine 22 ins. diam. brs. S58°E, 59 lks. dist.

In 1977 the Bureau of Land Management (BLM) conducted a remonumentation of certain original corner points in T.4S., R.32E., W.M., under Special Instructions dated May 3, 1957, Group 350. Their record states:

The 1/4 sec. cor. of secs. 23 and 24, determined from the original bearing trees: A pine, 21 ins. diam., bears N18°E, 69 lks. dist., with healed blaze. A pine, 21 ins. diam., bears S80°W, 59 lks. dist., with scribe marks 1/4 S BT visible on open blaze (Record, S58°E). At the corner point set an iron post, 28 ins. long, 2 1/2 ins. diam., 16 ins. in the ground, to solid rock, and in a mound of stone, 3 ft. base, to top, with brass cap mkd. (SEE DIAGRAM). Corner is located 3 lks. north of fence, extending E and W, and 35 lks. east of dirt road, 10 lks. wide, bears N and S.

Description of Corner Evidence Found:

Found a iron monument, set in a mound of stone, with a brass cap marked as shown in diagram. The monument is solid and in good shape.

Ponderosa Pine, 24" dia., with healed blaze chopped on but no scribing visible, bears N16°25'E, 44.8 ft. This original bearing tree is still alive and healthy. (Rec: N18°E, 45.54 ft.)

Ponderosa Pine, 22" dia., with scribing visible, bears S79°13'W, 38.2 ft. This original bearing tree is alive and healthy. (Org. Rec: S58°E, 59 lks. BLM Rec: S80°W, 38.94 ft.)

Description of monument and accessories I established to perpetuate the original location of this corner:

No work is needed on the monument.

From Which:

Douglas Fir, 12" dia., bears S33°30'E, 56.3 ft., scribed: 1/4 S24 BT

5/8"x30" rebar, set approximately 28 ins. in ground, with yellow plastic cap marked PLS 2405 bears, N30°45'W, 33.9 ft.

Measurements to BT and rebar taken with a magnetic compass, declination 20° East, and a nylon clad steel tape. Set steel fence post with Land Survey Monument (54-9) and Property Boundary (54-2) signs 5' north and south of the monument. Nailed a brass washer stamped PLS 2405 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs.

REGISTERED PROFESSIONAL LAND SURVEYOR

*Susan E. Newstetter*

OREGON JULY 25, 1989 SUSAN E. NEWSTETTER 2405

Renewal Date: 12/31/96

This work was performed by: Susan E. Newstetter PLS 2405 Witnessed by: Rick Saul and Rick Pewonka October 17, 1994

RECEIVED BY Umatilla County Surveyor Date 1-95 Rec'd By RK No. 95-15-B

Office of \_\_\_\_\_ County of \_\_\_\_\_ State of \_\_\_\_\_ I hereby certify that the within instrument was filed in this office for record on the \_\_\_\_\_ day of \_\_\_\_\_, 19\_\_\_\_ by \_\_\_\_\_

(COUNTY OFFICIAL)

(DEPUTY)

P-21